



सरदार वल्लभभाई राष्ट्रीय प्रौद्योगिकी संस्थान, सुरत
Sardar Vallabhbhai National Institute of Technology, Surat



ESTATE SECTION

PERCENTAGE RATE TENDER PAPER



TENDER: 2

PRICE BID

Name of work	:	Replacement of Damaged Windows at Bhabha Bhavan in SVNIT, Surat.
Name of Contractor	:	
Tender Fee	:	₹.500=00
Class of Registration	:	E1 – Class & Above
Issue of tender	:	29/11/2018 to 20/12/2018.
Receipt of tender	:	26/12/2018 upto 5:00 p.m.

The Director, S. V. National Institute of Technology, Ichchhanath, Surat – 395 007.

☎ 91-0261-2259571, 2259582-84

Name of Work :- Replacement of Damaged Windows at Bhabha Bhavan in SVNIT, Surat.

**SCHEDULE – B
(PWD SOR 2015-16)**

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
1	210.00	Dismantling doors,windows,ventilators etc. (wood or steel) shutters including chowkhats,architraves,holdfasts and other attachment etc. complete and stacking them within all lead and lift. (i) Not exceeding 3 Sq.mt. in area SOR- 20013A P/170 + 1% L.C. (118.00 + 1.18 = 119.18)	119.18		Each	25027.80	
2	300.00	Providing and fixing in position standard extruded Alluminium Three track (20 mm series) sliding shutter window having colour anodized section frame. Main outer frame size 95.00mm x 24.00mm x 1.17 mm (jindal section no:2459(New no.14053) @ wt. of 0.738 kg/mt). For shutters using top and bottom size 50 x 20 x 1.50 mm size, @ wt. of 0.642 kg/mt (jindal section no:20529) and interlock member size 50 x 29 x 1.50 mm size, @ wt 0.697 kg/mt(jindal section no:20531). Handle member size 50 x 20 x 1.50 mm, @ wt 0.571 kg/mt (jindal section no:20530). Two track sliding shutters (to cover full width) including providing heavy lock, 5 mm thick colour tinted float glass for glazing (structural Glass) fixed with transparent silicon gasket and providing and fixing wirenet of Stainless Steel wire of 304-grade of IS Gauge designation 85-G with wire of 0.56 mm diameter as a third sliding shutter with necessary screw including all required materials, labours and equipments as per details etc complete. As per R.A. + 1% L.C. (3417.00+ 34.17 = 3451.17)	3451.17		Smt	1035351.00	
3	165.00	Providing and fixing standared extruded of alluminium section of size 63.50mm x 38.10 mm x 1.95 mm (of jindal section no:4605, @ wt 1.094 kg/rmt.) with colour anodized alluminium frame with 5 mm thick transparent bronze colour tinted	1820.02		Smt	513282.00	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		float glass as details etc complete for Fix window. SOR-11031, P/124 + 1% L.C.(1802.00+ 18.02 = 1820.02)					
4	2.00	Brick work using common burnt clay building brick having crushing strength not less than 35kg/sq.cm. in superstructure above plinth level upto floor two level in CM 1:6 (1 cement : 6 fine sand). (B)Conventional SOR- 06002B + 06006B P/69&71 + 1% L.C. (3084.00 + 30.84 = 3114.84)	3114.84		Cmt		6229.68
5	360.00	Providing 15mm thick cement plaster in single coat on brick/concrete wall for interior plastering up to floor Two level finished even and smooth in (ii) cement mortar 1:4 (1 cement :4 sand) and finishing with a floating coat of neat cement slurry. SOR- 17002B + 17004 P/159 + 1% L.C. (136.30 + 1.36 = 137.66)	137.66		Smt		49557.60
6	390.00	20mm thick sand face plaster up to height of 10m from ground level consisting of 12mm thick backing coat of c.m.1:3 (1 cement : 3 coarse sand) finished with a top layer 8mm thick cement plaster 1:1 (1 cement : 1 coarse sand) etc complete. SOR - 17009 P/160 + 1% L.C. (208.00 + 2.08 = 210.08)	210.08		Smt		81931.20
			Total			₹...	17,11,379.28
			Say			₹...	17,11,380.00

I/ We am/ are willing to carry out the work at _____ % above/below percent (should be written in figures and words) of the estimated rates mentioned above.

Amount of my/ our tender works out as under.

Estimated amount

Put to tender ₹. _____

Deduct _____% below ₹. _____

Net ₹. _____

In words _____

Estimated amount

Put to tender ₹. _____

Add _____% above ₹. _____

Total ₹. _____

In words _____

Note

1. All work shall be carried out as per Public Works Department Handbook and other specifications of PWD/CPWD/SVNIT or as directed.
2. All the columns is Scheduled be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.
3. Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.
4. To be continued on additional sheets, if found necessary.

POSTAL ADDRESS OF CONTRACTOR

SIGNATURE OF CONTRACTOR

DATE: