UNDER POSTING OF CERTIFICATE

SARDAR VALLABHBHAI NATIONAL INSTITUTE OF TECHNOLOGY, SURAT

☎ 2259571, 2259582 - 84
FAX NO. 2227334, 2228394
GRAM : SVNIT
E-MAIL : director@svnit.ac.in

SVNIT

No.: SVNIT/G&CB/2026-27/NG/OW No.60 **Date: 16**/11/2026

To,

Sub: AN ENQUIRY for Supply, Fabrication and Installation of FRP Rani Laxmi Bai Sculpture and Kargil War Memorial at SVNIT Campus, Surat.

Dear Sir,

You are requested to quote your prices for **AN ENQUIRY for** Supply, Fabrication and Installation of FRP Rani Laxmi Bai Sculpture and Kargil War Memorial at SVNIT Campus, Surat**.** as per the **Annexure-1** enclosed herewith. The quotations may be sent to the undersigned in a sealed envelope and subscribed as: "Quotation with reference to Enquiry No. SVNIT/G&CB/2026-27/NG/OW No.60, dtd: 16/11/2026". Your quotation should reach the undersigned on or before dtd: 27/11/2026 in the office of Institute through post or in person. The Institute is not responsible for loss or postal delay of quotation.

The quotations should furnish the following in formations:

1) The brand or make of each item should be specifically stated and wherever necessary, Complete set of specifications and dimensions should be given.

2) If asked, samples are accompanying the quotations.

3) Sales tax, General tax, Central Sales tax, Custom duty, Insurance charges, Packing and Forwarding charges, if not included in the prices quoted, should be clearly specified.

4) The period of validity of the quotation may be specified. Offers subject to prior sale may please be avoided.

5) The completion period of the said work must be within 4-5 weeks from the date of receiving work order.

6) All concessions available to an educational institution should be specified and taken into account while quoting.

7) The Director and Faculty In Charge, G & CB Section reserves the right to accept stores which are not strictly in conformity with the specifications but otherwise found suitable.

Payment is normally made by cheque drawn on the S.V.N.I.T. Branch Office of State Bank of India, Surat-395007 within a period of thirty days from the date of receipt of stock.

Yours Faithfully,

For DIRECTOR

Name of the work:- Supply, Fabrication and Installation of FRP Rani Laxmi Bai Sculpture and Kargil War Memorial at SVNIT Campus, Surat.

ANNEXURE-I

Scope of work includes:

The scope shall include the design (if required), fabrication, supply, transportation, installation and fixing of the following FRP sculptures at the designated locations within SVNIT Campus.

Sr. No.	Description	Size / Dimensions	Quantity
1	FRP Sculpture of Rani Laxmi Bai mounted on a horse	Overall height: 10 ft.	1 No.
2	FRP Kargil War Memorial comprising a set of five Army personnel with suitable base	Life-size statues, approximately 6 ft. height each	1 Set

2. Detailed Technical Specifications

Parameter

Technical Specification

A. FRP Rani Laxmi Bai Sculpture (Mounted on Horse)

Parameter	Technical Specification
Subject	Rani Laxmi Bai mounted on a horse
Overall Height	Approximately 10 ft. (including horse and base, if applicable, to be clearly indicated by the vendor)
Material	Fibre Reinforced Plastic (FRP)
FRP Thickness	Minimum two-layer FRP construction using 450 GSM fibreglass mat
Resin	High-quality, weather-resistant polyester resin
Reinforcement	Internal MS structural framework for adequate strength and stability
MS Framework	Approximate weight: 180 kg, subject to structural design and stability requirements
Surface Finish	Smooth, uniform and detailed surface finish
Colour	UV-stabilized pigment with waterproof PU acrylic paint
Weather Resistance	Resistant to sunlight, UV radiation, rain, moisture and normal outdoor environmental conditions
Installation	Complete installation, fixing and anchoring at the designated location

B. FRP Kargil War Memorial (Set of Five Army Personnel)

Parameter	Technical Specification
Subject	Kargil War Memorial depicting five Indian Army personnel
Quantity	5 life-size statues (1 Set)
Height	Approximately 6 ft. per statue
Material	Fibre Reinforced Plastic (FRP)
FRP Thickness	Minimum two-layer FRP construction using 450 GSM fibreglass mat
Resin	High-quality, weather-resistant polyester resin
Reinforcement	Internal MS structural framework for adequate strength and stability
MS Framework	Approximate total weight: 300 kg for the complete set
Base	Suitable and aesthetically designed base for all five statues
Surface Finish	Detailed, smooth and uniform finish representing the uniforms, equipment and other features of Army personnel
Colour	UV-stabilized pigment with waterproof PU acrylic paint
Weather Resistance	Resistant to sunlight, UV radiation, rain and moisture
Installation	Complete assembly, fixing and anchoring at the designated location

3. Structural and Installation Requirements

1. The sculptures shall be designed and fabricated to withstand normal outdoor environmental conditions, including wind, rain and sunlight.
2. The internal MS framework shall provide adequate structural strength and stability.
3. All MS structural components shall be suitably treated with anti-corrosion primer and protective paint.
4. The sculptures shall be securely anchored to a suitable RCC foundation or approved supporting base.
5. All required foundation bolts, fasteners, supports, transportation and installation accessories shall be included in the quoted price.
6. The vendor shall ensure proper alignment, stability and finishing after installation.
7. The structural design and anchoring arrangement shall be submitted to SVNIT for approval before fabrication/installation, wherever required.

4. General Terms and Conditions

1. The vendor shall submit photographs of previously completed similar FRP sculpture projects along with the quotation.
2. The vendor shall submit material specifications, technical details and proposed fabrication methodology.
3. A preliminary design, colour scheme and proposed appearance shall be submitted for approval before commencing fabrication.
4. The final work shall be subject to inspection and approval by the SVNIT authorities.
5. The quoted rates shall be inclusive of fabrication, materials, transportation, loading/unloading, installation, foundation/anchoring arrangements, taxes and all other incidental charges. Any exclusions must be clearly specified.
6. The vendor shall provide a minimum **3-year warranty** against manufacturing defects, cracking, peeling of paint and deterioration of FRP under normal outdoor exposure.
7. The vendor shall rectify any defects observed during the warranty period at no additional cost to SVNIT.
8. The vendor shall complete the work within the stipulated period mentioned in the work order.

Note :- (i) the bidder free of cost should give Delivery.